WORK METHOD STATEMENT

NAME:	
ADDRESS:	
PROPOSED DEVELOPMENT: RETAINING WALL FXT	ENSION

We will be using the following equipment:

- Excavator for dredging the riverbed.
- Crane for putting in all 'H' beams & redgum sleepers.
- Tip truck for removing all waste.
- Bobcat excavation & clean up.
- Roller for compaction of retaining wall.

Any excess steel & redgum will be recycled .

, Deniliquin.

All waste from dredging will be removed from site & taken to:

- "Oakbank" 257 Four Post Lane, Deniliquin.
- The waste will be used to fill in an unwanted dam & is not in a flood prone area.